


The 8150 Series Fire Pump is designed to provide water to stand pipe, sprinkler, chemical mitigation, and hydrant systems for fire suppression in industrial and commercial facilities.

Features & Benefits

- Available in capacities from 1000 to 5000 GPM (1136 m³/hr).
- Pressures up to 288 PSI (203m).
- In compliance with NFPA #20, UL, FM, and ANSI.
- Performance and hydrostatic tests.
- Dynamic balance impellers.
- Dual volute casing balances radial forces on the shaft bearings.
- Space saving design.
- Easy maintenance and upkeep.
- Available in electric or diesel engine driven models.
- Standard construction: cast iron, bronze fitted.
- Clockwise or counterclockwise rotation is available to simplify pump room layout.
- Packed stuff box.
- Grease lubrication.
- Designed for low horsepower requirements.
- Available in 50 or 60 cycle.
- Suction and discharge flanges are on a common centerline.




Fire Pumps Series 8150

ACFP 8150A

**AC FIRE
PUMP**
a xylem brand

Series 8150

Part Name	Basic Construction Cast Iron, Bronze Fitted
Pipe Plugs (Casing)	Brass
Flush Piping	Copper
Packing Glands	304 Stainless Steel
Bolts (Gland)	Stainless Steel
Pipe Plugs (Brg. Hsg.)	Stainless Steel
Packing (Rings)	Graphite Impregnated Acrylic Yarn
Casing Assembly	Ductile Iron ASTM A536 GR 65-45-12
Casing Joint Gasket (Suction)	Paper (Vellumoid 505)
Casing Joint Gasket (Discharge)	Paper (Vellumoid 505)
Casing Joint Bolts	Steel Alloy
Dowel Pins (Casing)	Steel
Casing rings	Aluminum Bronze (ASTM B505, C954)
Shaft	Steel (SAE 1045)
Shaft Sleeves	Aluminum Bronze (ASTM B505, C954)
Shaft Sleeve Nuts	Aluminum Bronze (ASTM B505, C954)
Bearing Housing (Inboard)	Cast Iron (ASTM A48 Class 30A)
Bearing Housing (Outboard)	Cast Iron (ASTM A48 Class 30A)
Bearing Bracket	Cast Iron (ASTM A48 Class 30A)
Ball Bearing (Inboard)	Steel
Snap Ring	Steel
Deflectors	Rubber (Neoprene)
Lip Seals (Bearing)	Rubber (Buna "N")
Seal Cage	PTFE
Set Screws	Stainless Steel
Cap Screws	Steel
Grease Fittings (Bearing)	Steel
Key (Impeller)	Steel
Key (Coupling)	Steel
Impeller	Bronze (ASTM B584-875)
Spirol Pins (Casting Ring)	302 Stainless Steel
O-ring (Shaft Sleeve)	Rubber (Buna "N")
Retaining Ring	Steel



Pump Size

8x6x14F
16x10x22F



xylem
Let's Solve Water

Xylem Inc.
8200 N. Austin Avenue
Morton Grove, Illinois 60053
Phone: (847) 966-3700
Fax: (847) 965-8379
www.acfirepump.com

Xylem Inc.
55 Royal Road, Guelph, Ontario
N1H 1T1, Canada
Phone: (519) 821-1900
Fax: (519) 821-5316

A-C Fire Pump is a trademark of Xylem Inc. or one of its subsidiaries.
© 2017 Xylem Inc. ACFP 8150A January 2017